



LOGAN DIVING & SALVAGE

PRESS RELEASE

DECEMBER, 2009

ABACO, BAHAMAS SPECIALTY DREDGING PROJECT COMPLETED FOR AMERICAN BRIDGE & DISNEY @CASTAWAY CAY



SPECIALTY DREDGING SERVICES WERE REQUESTED TO DREDGE PORTIONS OF DISNEY'S CASTAWAY CAY HARBOR FOR AMERICAN BRIDGE ON AN UNSCHEDULED BASIS IN BETWEEN THE DISNEY MAGIC AND DISNEY WONDER PORT CALLS. LOGAN DIVING & SALVAGE MOBILIZED MEN AND DIVING EQUIPMENT TO THE ISLAND VIA AMERICAN BRIDGES PRIVATE PLANE AND SHIPPED HEAVY EQUIPMENT BY CHARTERED VESSEL FROM FT. LAUDERDALE. ONCE ON SITE, LDS CREWS UTILIZED AN 8" HYDRAULIC SUBMERSIBLE DREDGE TO REMOVE SEDIMENT INTO GEO TEXTILE TUBES FOR CONTAINMENT AND DISPOSAL. DIVERS UTILIZING SURFACE SUPPLIED DIVING EQUIPMENT AND HARDWIRE COMMUNICATIONS DREDGED THE PROJECT AREA TO DESIRED ELEVATIONS WORKING DAY AND NIGHT UNTIL COMPLETION. LOGAN DIVING & SALVAGE COMPLETED THE PROJECT AND DEMOBILIZED MEN AND EQUIPMENT DECEMBER 22, 2009 IN TIME FOR ALL EMPLOYEES TO SPEND THE HOLIDAYS WITH THEIR FAMILIES. HEAVY EQUIPMENT WAS RECOVERED IN JANUARY AND RETURNED TO LDS'S WAREHOUSE AND FACILITY IN JACKSONVILLE, FLORIDA.



GEO TUBE SPOIL AREA STATION FOR SUBAQUEOUS SEDIMENT CONTAINMENT